

	<b>RENTAL READY STANDARDS</b>	<b>FULLY RECONDITIONED STANDARDS</b>
<b>Engine (IC) or Motor (Electric) Operation</b>	runs smoothly, no leaks on floor; last scheduled maintenance performed within 250 hours Electric: traction motor brushes worn greater than 50% replaced	oil pan, rear main & front cover resealed as required; oil filter & engine oil replaced; leak down test performed Electric: traction, hydraulic, & steering motors Amp draw test performed; power cables & connection, terminals & studs, brushes & springs, bearings, and commutator repaired or replaced as required
<b>Compression</b>	even and within 15% on all cylinders	reconditioned as required
<b>Fuel</b>	passes emissions test; all intake hoses & fittings leak free & air tight; air filter clean & intact	carburetor & fuel pump, LP components, fuel lines & fittings repaired or replaced as required; fuel and air filters replaced; all connections inspected for air leaks and repaired as necessary
<b>Electrical System</b>	starting & charging systems operational; battery holds load  Electric: battery & cables clean, not frayed; battery compartment clean & corrosion free; battery connector not cracked or broken; contact tips not burned or sticking and replaced if more than 50% worn.	new battery installed if required; starter & alternator, voltage regulator, and all wiring checked and repaired or replaced if required; complete engine tune up with valve adjustment  Electric: battery load tested; specific gravity test; cell to cell voltage test; discharge & time cycle repaired as required; charger fully reconditioned as required; all wiring & switches repaired or replaced as required, all controller & contactor panels inspected and tested: all worn or damaged contact tips & bars and faulted control panel components replaced; all timers, cards & controllers treated, adjusted or replaced as required (rebuilt parts used where available)
<b>Cooling System</b>	pressure tested, no leaks; radiator fins cleaned; coolant cleaned & set to -30°F	radiator cleaned & repaired as required; hoses & belts replaced as required; new anti freeze installed
<b>Transmission/ Drive Axle/ Drive Unit</b>	stall test performed; fluid cleaned and filled; no hesitation when shifting	oil & filter replaced; transmission resealed as necessary; transmission pressure, gears, bearings and linkages repaired or replaced as required; pressure plate, differential, throw out bearings, clutch repaired or replaced as required; fluid drained and replaced
<b>Brakes</b>	linings not more than 60% worn; brakes do not pull or pulsate when applied; no fluid leaks; pedal does not drift as depressed; park brake holds truck with load on an incline or loading dock	brake shoes, wheel cylinders, master cylinder, brake lines & linkages repaired or replaced as required; parking brake repaired as required; tested under load and incline
<b>Steering</b>	axle repaired or replaced as required and greased within 225 hours; truck does not wander or self steer while driving	axle, power steer pump & cylinder, steering gear & hoses are repaired or replaced as required Electric: pump to motor coupling repaired or replaced as required
<b>Mast</b>	repaired or replaced as required; chains adjusted to specifications and replaced as required; no visible leakage on lift cylinders; lift hoses repaired or replaced as required	Assembly adjusted and re-shimmed as required; mast & carriage rollers and hoses & lift chains replaced as required; lift & tilt cylinders re-chromed and resealed as required
<b>Hydraulic System</b>	lines & hoses repaired or replaced as required, no leaks allowed; fluid cleaned and filled; breather in place and cleaned	pump & control valves replaced or rebuilt as required; oil & filters replaced; hoses & fittings replaced as required Electric: pump to motor coupling repaired or replaced as required
<b>Chassis/ Sheet Metal</b>	overhead guard in place and undamaged; sheet metal straight, no major scrapes or chips; seat cushions in good shape, no tears or cuts	unit completely steam cleaned; sheet metal repaired as required; exterior sanded, primed & painted with new decals; driver seat, steering wheel, gauges, pedal pads & controls replaced as required
<b>Tires</b>	replaced if more than 40% worn or excessive cuts	replaced if more than 20% worn
<b>General</b>	no leaks on floor from any reservoir, however dampness allowed; load tested and run for final inspection	load tested and run for final inspection
<b>Standard Warranty</b>	30 days parts and labor/90 days drive train parts and labor	90 days parts and labor or 100 hours parts and labor -- whichever occurs first



**Call us for your used equipment needs!**

**BROOKFIELD**  
800-236-2379

**Wisconsin Lift Truck Corp.**  
**GREEN BAY**    **JANESVILLE**  
800-236-7906    800-236-3380

**WAUSAU**  
800-236-3766

**Illinois Material Handling**  
**ELGIN**            **ROCKFORD**  
800-301-1121    800-236-6301

[www.wisconsinlift.com](http://www.wisconsinlift.com)

[www.imhwlt.com](http://www.imhwlt.com)